ADDRESS :1610 SKYVIEW DRIVE
HOUSTON, TEXAS 77043

CLIENT :MARCOS AYALA

BUYER : ~

LENDER : ~

A FORM SURVEY OF

LOT16, IN BLOCK 3 OF BRITT WAY ESTATES, A SUBDIVISION IN HARRIS COUNTY, TEXAS ACCORDING TO THE MAP OR PLAT THEREOF RECORDED UNDER VOLUME 116, PAGE 20 OF THE MAP RECORDS OF HARRIS COUNTY, TEXAS.

(BEARINGS BASED ON THE RECORDED PLAT)


NUM	DELTA	ARC	RADIUS	BEARING	DISTANCE
C1	18°40'16"	16.29'	50.00'	N08°08'08"E	16.22'
C2	71°19'44"	62.25'	50.00'	S53°08'08"W	58.30'
C3	24°14'16"	114.22'	270.00'	S76°40'52"W	113.37'
C4	6°03'28"	34.89'	330.00'	S67°35'28"W	34.87'
C5	90°00'00"	15.71'	10.00'	S43°48'00"W	14.14'

NUM	BEARING	DISTANCE
L1	N01°12'00"W	33.00'

BENCHMARK REFERENCE:

1. ALL ELEVATIONS SHOWN HEREON ARE TIED TO H.C.F.C.D. REFERENCE MARK NO. 210360, BRASS DISK IN CONCRETE, APPROXIMATELY LOCATED FROM THE INTERSECTION OF BRITTMORE ROAD AND SHADOW WOOD DRIVE, TRAVEL WEST ON SHADOW WOOD DRIVE APPROXIMATELY 0.2 MILES. MONUMENT IS LOCATED ON THE LEFT SIDE. ELEVATION = 91.40, NAVD 1988, 2001 ADJ..

SCALE : 1"=30'



NOTES:

1. SURVEYOR HAS NOT ABSTRACTED PROPERTY. SURVEY PERFORMED WITHOUT THE BENEFIT OF A TITLE COMMITMENT, AND IS BASED ON LEGAL DESCRIPTION(S) PROVIDED BY CLIENT; THERE MAY BE ADDITIONAL BUILDING LINES AND/OR EASEMENTS AFFECTING SUBJECT PROPERTY; ALL BUILDING LINES AND/OR EASEMENTS SHOWN HEREON ARE PER RECORDED PLAT UNLESS OTHERWISE SHOWN.
2. NOTHING IN THIS SURVEY IS INTENDED TO EXPRESS AN OPINION REGARDING OWNERSHIP OR TITLE.
3. THE WORD CERTIFY IS UNDERSTOOD TO BE AN EXPRESSION OF PROFESSIONAL JUDGMENT BY THE SURVEYOR, WHICH IS BASED ON HIS BEST KNOWLEDGE, INFORMATION AND BELIEF.
4. SURVEY IS CERTIFIED FOR THIS TRANSACTION ONLY; IT IS NOT TRANSFERABLE TO ADDITIONAL INSTITUTIONS OR SUBSEQUENT OWNERS.
5. THIS SURVEY IS BEING PROVIDED SOLELY FOR THE USE OF THE CURRENT PARTIES AND NO LICENSE HAS BEEN CREATED, EXPRESSED OR IMPLIED, TO COPY THE SURVEY EXCEPT AS IS NECESSARY IN CONJUNCTION WITH THE ORIGINAL TRANSACTION.

DATE: 01-27-25

REVISION: 01-31-2025 (FORM #2)

DRAWN BY: EJL/AB/EJL

APPROVED BY: DWG

PROJECT NO: GL-5291B

LEGEND:
H.C.M.R. - HARRIS COUNTY MAP RECORD
H.C.D.R. - HARRIS COUNTY DEED RECORD
H.C.C.F. - HARRIS COUNTY CLERK FILE
R.O.W. - RIGHT OF WAY
CM - CONTROL MONUMENT
I.R./I.P. - IRON ROD/IRON PIPE

Daniel W. Goodale

DANIEL W. GOODALE, R.P.L.S. NO. 4919

I HEREBY CERTIFY THAT THIS SURVEY WAS MADE ON THE GROUND UNDER MY SUPERVISION AND THAT IT CORRECTLY REPRESENTS THE FACTS FOUND AT THE TIME OF THE SURVEY. THERE WERE NO ENCROACHMENTS APPARENT ON THE GROUND EXCEPT AS SHOWN HEREON.

STATE OF TEXAS
REGISTERED
DANIEL W. GOODALE
4919
PROFESSIONAL
LAND SURVEYOR

FLOOD INFORMATION

PROPERTY "IS NOT" IN THE 100 YEAR FLOOD ZONE, THIS PROPERTY LIES IN ZONE "X" ACCORDING TO F.I.R.M. MAP NO. 48201C0640L DATED 06-18-2007.

BY GRAPHIC PLOTTING ONLY, WE DO NOT ASSUME RESPONSIBILITY FOR EXACT DETERMINATION. BEFORE ANY DEVELOPMENT PLANNING, DESIGN, OR CONSTRUCTION IS STARTED, THE COMMUNITY, CITY AND COUNTY IN WHICH SUBJECT TRACT EXISTS SHOULD BE CONTACTED. SAID ENTITIES MAY IMPOSE LARGER FLOOD PLAIN AND FLOODWAY AREAS THAN SHOWN BY F.I.R.M. MAPS THAT WILL AFFECT DEVELOPMENT.



GREENLEAF LAND SURVEYS, LLC
11500 NORTHWEST FWY
SUITE #160
HOUSTON, TEXAS 77092

GREENLEAF SURVEYING

DIR: 832-668-5003 FAX: 832-553-7210
FIRM # 10193977
orders@gllsurveys.com
www.greenleaflandsurveys.com